





## FIU PEDESTRIAN BRIDGE FAILURE

 PROJECT: Florida International University (FIU) intended to build a concrete pedestrian bridge to cross an 8-lane major arterial highway, SW 8th Street (Route US41), and Tamiami canal connecting the Maidique campus in Miami and the Sweetwater residential community where many students live.

The bridge was built using a method called Accelerated Bridge Construction, built in an adjacent yard and then moved onto place. This technique was intended to minimize disruption of traffic.

## FIU PEDESTRIAN BRIDGE FAILURE

- During construction the bridge failed on March 15, 2018 at about 1:46 PM.
- 7 occupied cars, stopped for a traffic light, were crushed by 930 tons of concrete and steel when the 174 ft main span dropped 18.5 ft.
  o 5 occupants died, 2 seriously injured, 3 minor injuries.
- ➢Six persons were working on the bridge at the time, ○1 fatally injured, 4 seriously injured, 1 minor injury.
- ➤The original project of \$19.4M was running \$2.6 over budget at failure and the completion date of July 2018 had slipped to Jan. 2019.
- Bridge related claims increased from \$42M to \$103M and forced the design/build contractor MCM into bankruptcy.

## PROJECT TEAM/ Contractual Relationships

### 1. <u>Permitting Agency</u>; Florida Department Of Transportation (FDOT)

- a. Issued a permit for traffic control during installation of the structure,
- b. Acted as a pass-through for FHWA funding and providing state funding for this \$19.4 million project,
- c. Conducted a routine preliminary review to ensure this project complied with the terms of the agreement (plans & specs) with the state,
- d. Authorized FIU to utilize the aerial space above the state road to build a structure.
- 2. <u>Owner;</u> Florida International University (FIU) intended to build a pedestrian bridge to cross an 8-lane highway and a canal.
- 3. <u>Design Concept</u>; **T.Y.LIN** provided FIU with the concept and criteria for design.
- 4. <u>Contractor;</u> MCM was hired by FIU as the design-build contractor.

## PROJECT TEAM/ Contractual Relationships

5. <u>Inspection;</u> **Bolton Perez & Associates (BPA)** provided Construction Engineering and Inspection (CEI) under contract with FIU.

- 6. <u>Engineer</u>; **FIGG** was hired by MCM as the "Engineer of Record" to design the bridge.
- 7. <u>Peer Review</u>; Louis Berger (LB) was hired by FIGG to provide an
- "independent" peer design review of FIGG's bridge design
- 8. <u>SBKTR;</u> Structural Technologies was hired by MCM to perform the post tensioning of the bridge.
- 9. <u>SBKTR;</u>Barnhart Crane was hired by MCM to move the adjacent casting yard to the final position over the road.

10. <u>SBKTR;</u> **Corradino Group** was contracted by BPA to inspect the post tensioning work.

# **Contractual Relationships**



## PROJECT TEAM/ Contractual Relationships

11. <u>Forensic Engineer</u>; **Wiss, Janney, Elstner Associates (WJE)** performed testing of full scale replicas of critical connections to determine the fundamental cause of the collapse.

12. <u>Federal Investigation</u>; **National Transportation Safety Board (NTSB)** Conduct accident investigation, number HWY18MH009.

13. Federal Investigation; Occupational Safety and Health

Administration (OSHA) Office of Engineering Services (OES)

- 1. FDOT did not require road closure during construction but a temporary detour was permitted for the moving and erection of the main truss. <u>Operations failure</u>
- 2. Design did not meet the FDOT requirement to include components. details and construction techniques that have greater than 5 years of FL use.
- 3. LB was not pre-qualified by FDOT to perform an "independent" peer design review of FIGG's bridge design. <u>Peer review failure</u>
  - a. LB did not provide 90% design review comments as required.

4. Cracking of the pre-cast/post-tensioned structure was not considered a safety issue of concern by FIGG (Engineer of Record), MCM (Design/Build Contractor), BPA (Construction Engineer & Inspector), for the span suspended over the open road. <u>Safety failure</u>

- Dynamic cracking is a sign of structural distress:
  - i. Feb 24, cracks appear in Member 11/12 node after form work is removed.

ii. Mar 10, Significant crack growth measured as main span is moved into position and PT rods are de-tensioned.

iii. Mar 15, A.M. Team meeting held at 0900, no safety concerns noted from concrete cracks.

iv. Mar 15, P.M. at 1346, bridge collapse.

5. The FIGG bridge engineer's analytical model underestimated design loads and overestimated design capacity resulting in factors of safety being significantly lower than originally assumed. <u>Design Failure</u>

a. EOR design fails:

i. Truss did not have a redundant load path, meaning if one element failed the entire structure failed.

ii. There was an inadequate peer review/oversight by LB and a conflict of interest eliminating "independence" of action.

6. The Constructability assessment did not include assessments of forces and loads at connections during all stages of construction, omitting the lift and place and 90% design concrete placement.

7. The post failure forensic engineer, WJE, determined the cause of failure was from not building the construction joints to FDOT standard construction specifications.

8. The design peer review by LB had inadequate knowledge and experience. They negotiated a contract with FIGG that had incomplete time and budgets to thoroughly focus on errors and omissions by FIGG throughout design development.

9. There was no Fail-Safe procedure or responsibility taken by the principal engineers to observe signs, detect and avoid a catastrophe.

10. A Final ethics determination will be made by the appropriate licensing board.

#### FIU BRIDGE LESSONS LEARNT

#### PRELUDE TO THE DISASTER

#### **STAGE 1: IN POSITION IN THE YARD**

Supported on its end diaphragms, truss members 2 and 11 are in compression. Post tensioning is correctly applied to put the bottom chord in compression also.



#### **STAGE 2: PREPARING FOR TRANSPORT**

South

pier

Without post tensioning, members 2 and 11 would now be tension (top image) hence temporary post tensioning is applied (all structure is now in compression).



East bound

8th Street

dinis sinis

pier

Westbound



contributed to creating a weakness at a critical location





### Diagonal Member 11

Deck













#### **SPMT Self Propelled Modular Transporters**

Ĩ

FLORIDA INTERNATIONAL UNIVERSITY

Read and

10111100

0

M

34

FIGG

SWEETWATER

FDOT

SU

-

-

TH

PROPERTY AND













![](_page_30_Picture_0.jpeg)

![](_page_31_Picture_0.jpeg)

![](_page_32_Picture_0.jpeg)

![](_page_33_Picture_0.jpeg)

![](_page_34_Picture_0.jpeg)

Six Victims: Navaro Brown, Bridge Worker Alexa Duran, FIU student Brandon Brownfield Osvaldo (Ozzie) Gonzalez Alberto Arias Rolando Fraga